

1091046

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-21,014-0000
100' W C W/2 SW SE SEC. 36, T 34 S, R 26 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2410 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LEE "36" WELL # 1A

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE 211.25

OPERATOR LICENSE # 32459

WELL TOTAL DEPTH 6500 FEET

OPERATOR: MEWBOURNE OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 6500' WITH 260 SX

NAME AND PO BOX 7698 SURFACE CASING: SIZE 8 5/8" @ 827' WITH 255 SX

ADDRESS TYLER, TX 75711 CONDUCTOR CSG: SIZE 20" @ 60'
SIZE 13 3/8" @ 219' WITH 233 SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR JERRY DUNKIN WELL SERVICES, INC LICENSE NUMBER 8733

ADDRESS PO BOX 389 ENID, OK 73702

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 21 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RUSSELL RANKIN **RECEIVED STATE CORPORATION COMMISSION**

(COMPANY NAME) JERRY DUNKIN WELL SERVICES, INC (PHONE) 580-237-6152 **APR 28 2000**

WERE: _____ CONSERVATION DIVISION
Wichita, Kansas

1ST PLUG SET CIBP @ 5850' WITH 2 SX CEMENT ON TOP. 2ND PLUG PULLED CASING TO 860' LOAD

HOLE WITH GEL SPOT 50 SX CEMENT. 3RD PLUG PULL TO 360' SPOT 40 SX CEMENT. 4TH PLUG

PULL TO 40' CIRCULATE LOST CEMENT TO SURFACE. HOLE STAYED FULL.

_____ PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 3:10 PM DAY: 21 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT _____

1ST PLUG SET CIBP AT 5850' WITH 2 SX CEMENT ON TOP. 2ND PLUG PULL CASING TO 860' LOAD

HOLE WITH GEL SPOT 50 SX CEMENT. 3RD PLUG PULL TO 360' SPOT 40 SX CEMENT. 4TH PLUG

PULL TO 40' CIRCULATE LOST CEMENT TO SURFACE. HOLE STAYED FULL.

REMARKS: USED COMMON CEMENT BY JERRY DUNKIN WELL SERVICES. RECOVERED 4800' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE 5/1/00 SIGNED _____
06/655
WV. REG.

(TECHNICIAN)

FORM CP-2/3