

1 050492

15-119-10253-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 3-6-58
C NE, SEC. 33, T 34 S, R 26 W/E
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

Lease Name Mary Taylor Well # 1

Operator: Gulf Oil Corporation

County Meade 203.45

Name & Address P. O. Box 12116

Well Total Depth 6260 feet

Oklahoma City, OK 73157

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1084

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Reeves & Wilson, Inc. License Number 6083

Address P. O. Box 963, Woodward, OK 73802

Company to plug at: Hour: 11:00 am Day: 3 Month: April Year: 19 85

Plugging proposal received from Sid Wilson

(company name) Reeves & Wilson (phone) 405-256-6023

were: 4 1/2" at 6260' PRTD 6100' Perfs at 6010-6024' in Morrow

1st plug set CIBP at 5980' with 2 sx cement

Spot cement through 4 1/2" casing with mud between plugs

2nd plug at 1184' with 50 sx cement

3rd plug at 500' with 40 sx cement

solid bridge

4th plug hulls - plug at 50' Plugging Proposal Received by Robert B. Tarbutton

cement to surface with 15 sx cement

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 3 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5980' with 2 sx cement, 2nd plug at -184' with

50 sx cement, 3rd plug at 500' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2300' 4 1/2" casing. Used common Class H cement by Reeves & Wilson
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)

DATE 4-16-85

INV. NO. 7749 4-3 MAY 09 1985