

1091066

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,651-0000  
C N/2 NE/4 SEC. 33, T 34 S, R 26 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MARY TAYLOR WELL # 33

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE 205.60

OPERATOR LICENSE # 3273 7/31

WELL TOTAL DEPTH 6326 FEET

OPERATOR: HERMAN LOEB

PRODUCTION CSG: SIZE 5 1/2" @ 6319' WITH 515 SX

NAME AND PO BOX 524

SURFACE CASING: SIZE 8 5/8" @ 1524' WITH 650 SX

ADDRESS LAWRENCEVILLE, IL 62439

CONDUCTOR CSG: SIZE " @ ' WITH SX

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187 MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 31 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 5480-86

SET CIBP @ 5412' WITH 2 SX CEMENT ON TOP. PUMP 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER PLUG, 150 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 31 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

SET CIBP @ 5412' WITH 2 SX CEMENT ON TOP. ALLIED PUMPED DOWN 8 5/8" CASING WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER PLUG, & 150 SX CEMENT.

MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 400#.

RECEIVED STATE CORPORATION COMMISSION

AUG 4 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 5 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

CONSERVATION DIVISION Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED

(TECHNICIAN)

FORM CP-2/3

DATE

8/10/00

WV. NO.

1060344

Handwritten signature and initials in a circle.