

To: 1 020677 S-24  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-119-20.637 - 0000  
C E/2 E/2, SEC. 31, T. 34 S, R 26 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060

2640 feet from S section line  
660 feet from E section line

Operator: Zinke & Trumbo, Ltd.  
Name &  
Address 1202 E. 33rd, Ste. 100  
Tulsa, OK 74105

Lease Name Fincham Well # 1-31  
County Meade 204.75  
Well Total Depth 6300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1217

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: \_\_\_\_\_ Day: 23 Month: 5 Year: 19 93

Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6300' w/350 sx cement, PBTD 6247', Perfs at 5922-32'

1st plug pump 1 sx hulls and 20 sx cement at 5850',

2nd plug pump 50 sx cement at 1240',

3rd plug pump 40 sx cement at 650',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5:30 p.m. Day: 24 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at 5850',

2nd plug pumped 50 sx cement at 1240', displaced with mud,

3rd plug pumped 40 sx cement at 500',

4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2814' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 6-8-93

INV. NO. 37859

Signed Glen P. Barber  
(TECHNICIAN)  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1993