

To: 051624 2-19  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,665 - 0000  
SE SE NW, SEC. 31, T 34 S, R 26 W/E  
2970 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060

Lease Name Fincham Well # 3-31

Operator: Zinke & Trumbo, LTD

County Meade

Name & Address 1202 E. 33rd, Ste. 100

Well Total Depth 6300 204.75 feet

Tulsa, OK 74105

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1479

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 19 Month: 2 Year: 19 93

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

work: 4 1/2" at 6297' w/300 sx cement, PBDT 6250'. Perfs at 5918-5934, 6000-6031'

1st plug pump 2 sx hulls and 20 sx cement to 5800',

2nd plug pump 50 sx cement at 1520',

3rd plug pump 40 sx cement at 600',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 5 p.m. Day: 19 Month: 2 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 5800',

Spotted plugs through casing:

2nd plug at 1520' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3018' of 4 1/2" casing. If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICE  
DATE MAR 04 1993  
INV. NO. 37446

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 23 1993  
CONSERVATION DIVISION  
Wichita, Kansas