

To: 1031400  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 119-20,626-0000  
SW NE SW, SEC. 29, T 34 S, R 26 W/E  
1400 feet from S section line  
3480 feet from E section line

TECHNICIAN'S PLUGGING REPORT 6-10  
Operator License # 4742

Operator: Texaco E & P Inc.  
Name:  
Address P.O. Box 2700  
Pampa, TX 79066-2700

Lease Name J.L. Beall Well # 2  
County Meade  
Well Total Depth 6200 201.50 feet  
Conductor Pipe: Size 16" feet 85  
Surface Casing: Size 8 5/8" feet 1318

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Dowell License Number \_\_\_\_\_  
Address P.O. Box 1254, Perryton, TX 79070

Company to plug at: Hour: 10:40 a.m. Day: 10 Month: 6 Year: 19 96

Plugging proposal received from Roy Hoover  
(company name) Texaco E & P Inc. (phone) 316-263-8753

Work: 4 1/2" at 6199' w/365 sx cement, PBSD 6150', TOC 3016', Perfs at 3158-6085'  
1st plug pump 50 sx cement into perfs at 3158-63 & 3198-3203' plus the capacity of 4 1/2" casing  
(170 sx). Leave 4 1/2" casing full to surface,  
2nd plug pump 248 sx cement down 8 5/8" X 4 1/2" annulus to 1331'.

RECORDED  
KANSAS CORPORATION COMMISSION  
JUN 19 1996

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN) CONSERVATION DIVISION WICHITA, KS

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 12:52 p.m. Day: 10 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 215 sx cement. Maximum pressure 1000 psi and shut in 1000 psi.  
2nd plug pumped down 4 1/2" X 8 5/8" annulus with 262 sx cement. Maximum pressure 600 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Dowell. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (operator) did not observe this plugging.

DATE 6-25-96  
WELL NO. 45874  
6-10

Signed Steve Durrant  
(TECHNICIAN)