

To: 1 090159
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,209 ¹⁻¹⁷ ¹⁻⁰⁰⁰⁰ ⁷²

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444

Operator: Charter Production Company
Name & Address 224 E. Douglas, Suite 400
Wichita, KS 67202

C NE, SEC. 16, T. 34 S, R. 26 W/E

3960 feet from S section line

1320 feet from E section line

Lease Name Lee Painter Well # 1

County Meade ^{196.62}

Well Total Depth 6050 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1490

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12 p.m. Day: 17 Month: 1 Year: 19 92

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 6050', PBD 6010', Perfs at 5855-6011'

1st plug set CIBP at 5800' and dump 2 sx cement on top,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150

sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1992
1-23-92
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 17 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5800' and dumped 2 sx cement on top,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Maximum pressure 1250 psi and shut in 750 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1440' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

DATE JAN 29 1992

REV. NO. 34393

Signed [Signature] (TECHNICIAN) ^{RMS}