

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21061-00-00  
Spot: CNW Sec/Twnshp/Rge: 14-34S-26W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease/Unit Name: EASTERDAY Well Number: 2  
County: MEADE Total Vertical Depth: 5950 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size 20 feet: 100  
Surface Casing: Size 8.625 feet: 1462  
Production: Size feet:  
Liner: Size feet:

*8193.38*

Well Type: DH UIC Docket No: Date/Time to Plug: 09/04/2001 11:00 PM  
Plug Co. License No.: 30684 Plug Co. Name: ABERCROMBIE RTD, INC  
Proposal Rcvd. from: BILL CRAIG Company: ABERCROMBIE RTD, INC Phone: (316) 262-1841

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 09/05/2001 4:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED  
SEP 10 2001  
KCC WICHITA

INVOICED  
DATE 9-11-01  
INV. NO. 2002060443

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES.

Plugged through: DP

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

SEP 06 2001

Form CR-273

*MP*