

1 060749

API NUMBER 15- 119-20,249 - 0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NE SE , SEC. 33 , T 34 S, R 29 (W/E)

2300 feet from (S) section line

1250 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5575

Lease Name Adams Well # 2-33

Operator: Mesa Petroleum Company

County Meade

Name & Address P. O. Box 2009

Well Total Depth 6380 207.35 feet

Amarillo, TX 79105

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1532

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 11:00 am Day: 18 Month: December Year: 19 85

Plugging proposal received from Bob Sargent's

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6375' Perfs at 5995-98'; 6013-17'; 6024-29'

Pump through 4 1/2" with mud between plugs

1st plug at 6029' with 2 sx hulls and 30 sx cement

2nd plug at 2620' with 100 sx cement

4th plug at 700' with 40 sx cement

3rd plug at 1580' with 50 sx cement

solid bridge - hulls - plug

5th plug at 40' -- cement to surface

with 10 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 5:00 pm Day: 20 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 6029' with 2 sx hulls and 30 sx cement, 2nd plug at

2620' with 100 sx cement, 3rd plug at 1580' with 50 sx cement, 4th plug at 700' with

40 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement.

Remarks: Recovered 3205' 4 1/2" casing. Used Common Cement by Sargent's  
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION Paul A. Luthi (TECHNICIAN)

DATE DEC 27 1985

DEC 27 1985

INV. NO. 11745