

6-30

To: 1 051178
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,011 - 0000
C NW SE, SEC. 28, T 34 S, R 29 W NEK
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6568
Operator: Kaiser-Francis Oil Company
Name & Address: P.O. Box 21468
Tulsa, OK 74121-1468

Lease Name H.G. Adams Well # 1-28
County Meade 204.75
Well Total Depth 6300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1374

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Reeves Casing Pulling License Number _____
Address _____

Company to plug at: Hour: 11 a.m. Day: 30 Month: 6 Year: 19 89

Plugging proposal received from Rob Reeves
(company name) Reeves Casing Pulling (phone) 405-677-8347

were: 4 1/2" at 6100' PBD 6067' Perf at 5970-6006'
1st plug set CIBP at 5900' with 2 sx cement on top,
2nd plug pump 30 sx cement at stub, 3rd plug pump 50 sx cement at 1425-1325',
4th plug pump 25 sx cement at 650',
5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5 p.m. Day: 30 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5900' with 2 sx cement on top,
2nd plug pumped 30 sx cement at 2300',
3rd plug pumped 50 sx cement at 1425'-1325',
4th plug pumped 25 sx cement at 650',
5th plug pumped 10 sx cement at 40-0'. Mud between plugs.

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 - 5 1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used Class H cement by B.J. Titan. Recovered 2437' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If applicable) observe this plugging.

DATE 7-6-89

Signed Richard W. Tracy
(TECHNICIAN)

INV. NO. 25214
6-30