

To: 051780 2-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,146 - 0000
SE SE NW, SEC. 28, T. 7 S. R. 29 N/8
2970 feet from S section line
2974 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7457
Operator: Elder & Vaughn
Name:
Address P.O. Box 18938
Oklahoma City, OK 73154

Lease Name Mohler Well # 1
County Meade
Well Total Depth 6050 196.63 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 711

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Petrofield Services Corp. License Number 31330

Address 110 S. Hartford, Tulsa, OK 74120

Company to plug at: Hour: 9 a.m. Day: 11 Month: 2 Year: 1994

Plugging proposal received from Jack Vaughn

(company name) Elder & Vaughn (phone) 405-842-8877

Work: 5 1/2" at 6054' w/125 sx cement, PBTD 6032', Perfs at 5963-65, 5978-88'

1st plug set CIBP at 5900' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 14 Month: 2 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5900' and dumped 2 sx cement on top,
Plugged through tubing:

2nd plug at 711' with 100 sx cement,

3rd plug at 60' with 30 sx cement.

Remarks: Used common cement by Petrofield Services Corp. Recovered 1317' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did/observe) observe this plugging.

DATE FEB 22 1994

INV. NO. 39989
2-14

Signed Richard W. Lewis
(TECHNICIAN)