

To: 1 020306
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-27 15-119-20277-0000
API NUMBER 15- 119- 20277

SW, SEC. 27, T 34 S, R 29 W/E
1250 feet from S section line
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # MESA 04824
Operator: MESA OPERATING LTD PMA
Name & Address: P.O BOX 2009
Marillo Texas
79189

Lease Name ADAMS Well # 1-27
County Meade 206.31
Well Total Depth 6348 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1530

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor SARGENTS CASINO Pulling License Number 6547
Address 620 S LINCOLN Liberal, KANSAS 67901

Company to plug at: Hour: 10 AM Day: 27 Month: MARCH Year: 19 90

Plugging proposal received from _____
(company name) _____ (phone) _____

were: 5 1/2 AT 6348' PBD 6301, Perfs 5872-5910, 5972-6248

① Load hole mud set CIBP AT 5850 with 2 sy cement on top. Shoot pipe at free point. Fill hole with heavy mud ② Pump 50 sy at 1577' 1425' ③ Pump 30 sy at 650' 490' ④ Plug Pump 10 sy at 30 ft to O. Cut off 8 5/8 3' below GL. & weld cap on

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part X None _____

Operations Completed: Hour: 4:30 PM Day: 27 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT ① set CIBP AT 5850, dumped 2 sy cement on plug with bailer. Load Hole with mud, shot pipe of 3218 and pull.

② Run tubing to 1577. ③ Pump 50 sy at 1577 - 1425

Pull tubing to 650 3rd Plug Pump 30 sy at 650 - 490.

④ Run 10 sy at 30 ft to O. Cut off 8 5/8 weld cap on 3" below GL

Heavy mud between all plugs. Recovered 3218 at 15 1/2

Remarks: RECEIVED all cement plugs, useful common cement Portland cement
STATE CORPORATION COMMISSION (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 4-6-90
INV. NO. 2778

4/6/90
recd

Signed Glenn R. Barber (TECHNICIAN)