

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20044-00-00
Spot: SWNE Sec/Twnshp/Rge: 31-34S-30W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: ADAMS D Well Number: 1
County: MEADE Total Vertical Depth: 4400 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet:
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1280 WITH 730 SX CMT
Address: 17001 NORTHCHASE DRIVE Production: Size 4.5 feet: 4399 WITH 125 SX CMT
HOUSTON, TX 77060 Liner: Size _____ feet: \$143.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2001 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4300'. 1ST PLUG AT 1300' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 35 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/23/2001 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBTD 4364'. PERFS AT 4346-4348'. SET CIBP @ 4300'. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 1300' PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE TO 660' PUMP 25 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40' PUMP 10 SX CMT.

RECEIVED
SEP 07 2001
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2000' OF 4 1/2" CASING.
Plugged through: CSG

District: 01 Signed Jim Holland PART II
(TECHNICIAN)
INVOICED SEP 06 2001
DATE 9-7-01
INV. NO. 2002060428 *MP*

Form CR-20 