

1090197

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,046-0000

C SW NW 1/4, SEC. 31, T 34 S, R 30 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5361

Lease Name ADAMS Well # 3

Operator: Blaik Oil Company

County MEADE

Name & Address 5825 Grand

Well Total Depth 4400 143.00 feet

Oklahoma City, OK 73116

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1259

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number N/A

Address Box 1598, Liberal, KS 67901

Company to plug at: Hour: 3 p.m. Day: 12 Month: June Year: 1984

Plugging proposal received from Rex Ward

(company name) Blaik Oil Company (phone) 405-758-3580

were: Rig up and perforate 4 1/2 casing at 1300 feet, rig up Halliburton cementing and circulate 325 sacks of Class A cement by pumping down the 4 1/2 and back up the annulus.

Plugging Proposal Received by

R. B. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 3 pm Day: 15 Month: June Year: 1984

ACTUAL PLUGGING REPORT Well was flowing from annulus at 600 lbs. pressure. Fittings and

valves installed to choke flow while cementing. Halliburton rigged up and pumped 386 sacks

of Class A cement down the 4 1/2. Cement did not circulate. Shut well in for night.

Returned 6-14-84 and tagged top of cement in 4 1/2 at 50 feet. Filled with 5 sacks. Annulus

still flowing at 600 lbs. Halliburton rigged up to 8 5/8 and pumped at 800 lbs pressure

another 395 sacks Class A cement. Pump pressure finally dropped to 200 lbs. and that

Remarks: was the shut-in pressure. Well checked on 6-15-84 had no flow and considered

(if additional description is necessary, use BACK of this form.) plugged.

INVOICED

DATE 7-16-84

INV. NO. 2536

6-15

JUL 17 1984

JUL 11 1984

CONSERVATION DIVISION
Wichita, KS

RECEIVED
STATE CORPORATION COMMISSION Signed

R. B. Barluttan
(TECHNICIAN)