

1 060445

API NUMBER 15- 119-20,028-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SW NW, SEC. 30, T 34 S, R 30 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5461

Lease Name Adams "C" Well # 1-30

Operator: Horizon Oil & Gas Co.

County Meade 142.35

Name & Address Box 7

Well Total Depth 4380 feet

Spearman, TX 79081-0007

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1250 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 1:00 pm Day: 17 Month: December Year: 19 84

Plugging proposal received from Curtis Covington

(company name) Horizon (phone) 806-659-2544

logs: 4 1/2" set at 4378' PBD 4280' Perfs at 4190-96'

1st plug pump 2 sx hulls and 20 sx cement to bottom covering perfs. Shot off pipe and pumped additional plugs through 4 1/2"

2nd plug at 2000' with 40 sx cement 3rd plug at 1270' with 50 sx cement 4th plug at 660' with 40 sx cement, 5th plug at 40' to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luttich
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 pm Day: 20 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to bottom covering perfs.

Shot off pipe and pumped additional plugs through 4 1/2" casing. 2nd plug at 2000' with 40 sx cement, 3rd plug at 1270' with 50 sx cement, 4th plug at 660' with 40 sx cement.

5th plug at 40' to surface with 10 sx cement. Cement did not set up - still flowing a

little salt water. 12-20-84 - Went back in hole with tubing and drilled down to 1250' and hit solid cement. Pumped cement through tubing. Pumped 50 sx cement into a 1250',

2nd plug pumped 40 sx cement to 660', 3rd plug 40-0' pumped 10 sx cement

Remarks: Used class H cement by Sargent's. Recovered 2000' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-14-85

INV. NO. 6422

Signed Paul A. Luttich
(TECHNICIAN)