

1091061

TO: STATE CORPORATION COMMISSION API NUMBER 15-119-21,025-0000
110'E 155'N W/2 NE NE SEC. 30, T 34 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 505 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 880 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HOLMES WELL # 1-30

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 198.25

OPERATOR LICENSE # 30604 WELL TOTAL DEPTH 6100 FEET

OPERATOR: RAYDON EXPLORATION, INC. PRODUCTION CSG: SIZE " FEET

NAME AND 9400 N BROADWAY, SUITE 400 SURFACE CASING: SIZE 8 5/8" @ 1659' WITH SX

ADDRESS OKLAHOMA CITY, OK 73114 CONDUCTOR CSG: SIZE " @ ' 1

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572

ADDRESS P.O. BOX 1856 LIBERAL, KS 67905-1856

COMPANY TO PLUG AT: HOUR: 4:30 PM DAY: 16 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM HELEN W/CROWN CONSULTING

(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

WERE:

1ST PLUG AT 1680' WITH 50 SX CEMENT. 2ND PLUG AT 500' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 7:30 PM DAY: 16 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1680' WITH 50 SX CEMENT. 2ND PLUG AT 500' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I DID NOT OBSERVE THIS PLUGGING

INVOICED 7/5/00 SIGNED [Signature] (TECHNICIAN) FORM CP-2/3
WV. NO. 1060005
JUL 03 2000 RECEIVED STATE CORPORATION COMMISSION
CONSERVATION DIVISION Wichita, Kansas