

1 080169

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,662-0000

SW NE, SEC. 7, T. 34 S, R. 30 (W/E)

1980 feet from N/E section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Wickwire TrustWell # 1

Operator: Petroleum, Inc.

County Meade

Name & Address 300 West Douglas

Well Total Depth 6420 208.65 feet

R. H. Garvey Building

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 1512 1450

Abandoned Oil Well Gas Well Input Well SWD Well D&A^X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Douglas and Broadway, Wichita, KS 67202

Company to plug at: Hour: 6:00 am Day: 10 Month: July Year: 19 84

Plugging proposal received from Bill Daugherty

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1560' with 50 sx cement

2nd plug at 700' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by J. A. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 am Day: 10 Month: July Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement, 2nd plug at 700' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10

sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse

hole with 10 sx cement, plugged water well with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1984

Remarks: Used 60/40 Pozmix 2% gel by Halliburton CONSERVATION DIVISION
(If additional description is necessary, use BACK of this report.)

Signed J. A. [Signature] (TECHNICIAN)

INVOICED

DATE 7-18-84

INV. NO. 2562
7-10