

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20582-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 8-33S-27W
1079 feet from N Section Line, 1272 feet from E Section Line
Lease Name: THIESSEN D E Well #: 2
County: MEADE Total Vertical Depth: 5797 feet

Operator License No.: 30417
Op Name: AEXCO PETROLEUM, INC.
Address: 1600 BROADWAY, STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5792	1538	WITH 285 SX CMT
SURF	8.625	1323		WITH 690 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/11/2015 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 4700' WITH 2 SX CMT. SPOT 50 SX CMT AT 1350'. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2015 3:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

TBG PARTED AT 2600'. CLEANED OUT TO 4350'-4380'. RAN TBG IN HOLE TO 4380' & PUMPED 30 SX CMT. 1ST PLUG AT 1350' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5599	5609		

Remarks: USED CLASS A CEMENT BY SARGENT LILLARD.

Plugged through: CSG

4/1/15CKM

District: 01

Signed Larry Harris ALB
(TECHNICIAN) JA

RECEIVED
MAR 25 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 30 2015
CONSERVATION DIVISION
WICHITA, KS