

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-20504-00-00
Spot: SWNENWSE Sec/Twnshp/Rge: 22-30S-35W
2011 feet from S Section Line, 1937 feet from E Section Line
Lease Name: HOOPER Well #: 4-22
County: GRANT Total Vertical Depth: 5540 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5370		WITH 2 SX CMT
PROD	5.5	5540	1982	WITH 725 SX CMT
SURF	8.625	1620		WITH 900 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2015 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 5370' WITH 2 SX CMT. PLUG AT 1640' WITH 10 SX GEL & 50 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2015 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5370' WITH 2 SX CMT. 1ST PLUG AT 1650' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5406	5416		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed *Larry Harris* PIRT-II
(TECHNICIAN)

RECEIVED
MAR 26 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS