

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20609-00-00
Spot: SESW Sec/Twnshp/Rge: 2-32S-34W
619 feet from S Section Line, 3300 feet from E Section Line
Lease Name: FITZGERALD A Well #: 1-2
County: SEWARD Total Vertical Depth: 5720 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4130		WITH 2 SX CMT
CIBP		4190		
CIBP		4300		
CIBP		4500		
CIBP		4760		
CIBP		4900		
DVT		3191		WITH 300 SX CMT
PROD	5.5	5712	2509	WITH 300 SX CMT
SURF	8.625	1730		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 4130' WITH 2 SX CMT. PLUG AT 1780' WITH 10 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 03/18/2015 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4130' WITH 2 SX CMT. 1ST PLUG AT 1789' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 549' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5548	5566		
4830	4836		
4676	4682		
4408	4412		
4196	4202		
4178	4183		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

RECEIVED

MAR 25 2015

Signed

Received
KANSAS CORPORATION COMMISSION

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS

4/1/15 CKM

District: 01

KCC DODGE CITY