

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-20995-00-02  
Spot: E2W2SWSW Sec/Twnshp/Rge: 1-32S-34W  
660 feet from S Section Line, 4745 feet from E Section Line  
Lease Name: BOLES UNIT E Well #: 1-2  
County: SEWARD Total Vertical Depth: 5700 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
CIBP		5420		
MSCC		3200		
PROD	5.5	5700	1814	WITH 845 SX CMT
SURF	8.625	1694		WITH 770 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2015 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 4150' WITH 2 SX CMT. PLUG AT 1730' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/20/2015 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PLACED 2 SX CMT ON TOP OF EXISTING CIBP @ 4150' WITH DUMP BAILER. 1ST PLUG AT 1740' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 540' WITH 40 SX CMT. 3RD PLUG AT 45' CIRCULATED CMT TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4412	4425		
4243	4260		
4208	4220		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED  
MAR 26 2015  
KCC DODGE CITY

Signed

Larry D Harris  
AERT

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAR 30 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

4/1/15 CKM