

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-10013-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 18-30S-8W
4911 feet from S Section Line, 5007 feet from E Section Line
Lease Name: MESSENGER B Well #: 2-18
County: KINGMAN Total Vertical Depth: 4345 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4345	2266	150 SX
SURF	8.625	408		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2015 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: ALLIANCE WELL SERVICE Phone: _____

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/27/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 4180' CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 2266' PULLED CASING. RAN TUBING INTO 1365' SPOTTED 35 SXS CEMENT WITH 3% CC. RAN TUBING TO 849' SPOTTED 35 SXS CEMENT WITH 3% CC. RAN TUBING TO 455' CIRCUALTED TO SURFACE WITH 178 SXS CEMENT.

Remarks: ALLIED CEMENTING OUT OF MEDICINE LODGE, DID CEMENTING USING CLASS A. PLUGGED DUE TO DENIED TA.

Plugged through: TBG

4/1/15 CKM

District: 02

Signed

B. J. Hope

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JK