

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21207-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 21-31S-30W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: LAND A Well #: 2-21
County: MEADE Total Vertical Depth: 5990 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 5400 | | WITH 2 SX CMT |
| PROD | 4.5 | 5990 | 2580 | WITH 353 SX CMT |
| SURF | 8.625 | 1706 | | WITH 550 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/13/2015 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 5400' WITH 2 SX CMT. PLUG AT 1750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2015 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

3/13/15: SET CIBP @ 5400' WITH 2 SX CMT. 1ST PLUG AT 1750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. LOST CIRCULATION. SHUT DOWN. 3/16/15: RAN TBG IN HOLE & TAGGED TOP OF CMT AT 480' & PUMPED 50 SX CMT. PULLED TO 40' & PUMPED 20 SX CMT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5598 | 5606 | | |
| 5586 | 5594 | | |
| 5552 | 5554 | | |
| 5541 | 5548 | | |
| 5532 | 5534 | | |
| 5511 | 5520 | | |
| 5488 | 5504 | | |
| 5462 | 5482 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/1/15 CKM

District: 01

Signed Gary S. Lewis PERT II
(TECHNICIAN)

RECEIVED
MAR 26 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
MAR 30 2015
CONSERVATION DIVISION
WICHITA, KS