

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service Oil has this

date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Thonhoff "B" Well No. 1

Location: App C SW Sec. 4 Twp. 35 Rge. 27 ~~(E)~~ (W)

County: Meade Total Depth 6865' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

8 5/8" to 1251' circulated w/ cement. 5 1/2" to 6862' cemented.

Top perforations 3199' Plug bottom w/ 20 sacks cement.

Top pf cement. 2800' Mud 2800' to 312'

Spot 35 sacks cement 312' to 205' Mud 205' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent