

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSASVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1964

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Price of An-son Corporation has this

date requested permission to plug the following described well:

Mr. Price guarantees payment of the plugging fee.Operator's full Name: An-son CorporationComplete Address: 3814 N. Santa Fe, Okla. City, Okla.Lease Name: Fincham Well No. A-1Location: C SW Sec. 2 Twp. 35S Rge. 27 (E) (W)County Meade Total Depth 6519' Oil Well XGas Well      Input Well      SWD Well      D & A X Lost Hole     Mr. Price was instructed to plug the well as follows:8 5/8"-1537' Circulated w/cement.Mud 6519' to, 5500' Spotted 25 Sax. cement 5500' to 5400'Mud 5400' to 700' Spotted 35 Sax. cement 700' to 600'Mud 600' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

  
Conservation Division Agent