

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Maxey of Pioneer Production has this

date requested permission to plug the following described well:

Mr. Maxey guarantees payment of the plugging fee.Operator's full Name: Pioneer ProductionComplete Address: Box 2542, Amarillo, TexasLease Name: E.A. Sutherland Well No. 1Location: C NE SW Sec. 8 Twp. 35 Rge. 26 XX (E) (W)County: Meade Total Depth 6400' Oil WellGas Well X Input Well SWD Well D & A X Lost Hole Mr. Maxey was instructed to plug the well as follows:8 5/8" to 721' circulated w/ cement. 2 7/8" to 6358' cementedTop perforations 6073' Plug bottom w/ 10 sacks cement.Top of cement 5800' Mud 5800' to 700'Spot 35 sacks cement 700' to 600'. Mud 600' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Green
Conservation Division Agent