

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
APR 28 1967  
4-28-67  
CONSERVATION DIVISION  
Wichita, Kansas  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Duncan of Lone Star Exploration has this date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: Lone Star Exploration Inc.

Complete Address 2010 Republic Nat'l Bk. Bldg. Dallas, Texas

Lease Name: Noble Cook Well No. 1

Location: C NW SW Sec. 9 Twp. 35 Rge. 22  (E)  (W)

County Glark Total Depth 5746' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Duncan was instructed to plug the well as follows:

13 3/8" to 425' circulated w/ cement. 8 5/8" to 2480' cemented

5 1/2" to 5738' cemented No Perf. 8' of open hole

Plug Bottom w/ 25 sacks cement. Top of cement 5638'

Mud 5638' to 475' Spotted 50 sacks cement 475' to 375'

Mud 375' to 30' Plug, Hulls & 15 sacks cement 30' to 0'

Very truly yours,

Edmund E. Green  
Conservation Division Agent