

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 12 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pierce of Union Oil of Calif. has this

date requested permission to plug the following described well:

Mr. Pierce guarantees payment of the plugging fee.

Operator's full Name: Union Oil of California  
1868 Lincoln St. Denver, Colo. 80203  
Complete Address: 2000 Classen Center, Oklahoma City, Oklahoma

Lease Name: C. H. Tuttle "D" Well No. 1

Location: C NW NW Sec. 8 Twp. 35 Rge. 22 (W)

County Clark Total Depth 5935 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Pierce was instructed to plug the well as follows:

1 1/2" 3/8" to 558' circulated w/ cement. 5 1/2" to 5747' cemented

Top perforations 5630' Plug bottom w/ 20 sacks cement

Top of cement 5550' Mud 5550' 550'

Spotted 40 sacks cement 550' to 480' Mud 480' to 30'

Plug, Hulls & 15 sacks cement 30' to 0'

Very truly yours,

Edgar A. Green  
Conservation Division Agent