

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1969 9-8-69
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Goostree of Midwest Oil Corp. has this

date requested permission to plug the following described well:

Mr. Goostree guarantees payment of the plugging fee.

Operator's full Name: Midwest Oil Corporation

Complete Address: 1700 Broadway, Denver, Colorado

Lease Name: Interstate Cattle & Loan Co. Well No. 1

Location: SW NW Sec. 7 Twp. 34 Rge. 43 (W)

County Morton Total Depth 4812' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Goostree was instructed to plug the well as follows:

8/8/8" 13 3/8" to 586' circulated w/ cement. 8 5/8" to 1373' circulated w/ cement.

Mud 4812' to 900' Spot 35 sacks cement 900' to 800'

Mud 800' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent