

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 18 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern has this
 date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828, Liberal, Kansas

Lease Name: Linscott Well No. 1

Location: C NW Sec. 33 Twp. 34 Rge. 43 (E) (W)

County Morton Total Depth 3075' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sutton was instructed to plug the well as follows:

7" casing to 604' circulated w/ cement. 4 1/2" to 2730' cemented.

Perforations squeezed off. Top of cement 1900'.

Mud 1900' to 600' Spot 35 sacks cement 600' to 450'

Mud 450' to 75' Plug, Hulls & 15 sacks cement 75' to 0'.

Very truly yours,

Edgar J. Eves
 Conservation Division Agent