

RECEIVED

APR 14 2003

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

KCC WICHITA WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-20472-~~10001~~ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Operating Company, LLC KCC LICENSE # 33168
(owner/company name) (operator's)

ADDRESS 125 N. Market Suite 1000 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (620) 886-5605 #27

LEASE Holmes WELL# H-1 SEC. 33 T. 34 R. 13 (East/West)

- - SE - SE SPOT LOCATION/QQQQ COUNTY Barber

701 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

645 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ___ GAS WELL X D&A ___ SWD/ENHR WELL ___ DOCKET# ___

CONDUCTOR CASING SIZE ___ SET AT ___ CEMENTED WITH ___ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 457' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5094' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perf 4984' to 4990' & 4904' to 4914' & 4875' to 4902'

ELEVATION 1869 T.D. 5094' PBDT 4975' ANHYDRITE DEPTH ___
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR ___ CASING LEAK ___ JUNK IN HOLE ___

PROPOSED METHOD OF PLUGGING: Set CIBP @ 4875', Place 4 sax cement w/ dump bailer. Cut & pull csj. Spot 50 sax @ 600', 40 sax @ 300' & 20 sax @ 40' to surface.

Use 60/40 poz + 6% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? ___

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (620) 886-5605 #27

ADDRESS P.O. Box 168 City/State Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Clarke Corporation KCC LICENSE # 5169 5105
(company name) (contractor's)

ADDRESS Medicine Lodge, KS 67104 PHONE # (620) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4/21/04

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4/11/03 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)



Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Woolsey Operating Company, LLC
125 N. Market, Suite 1000
Wichita, KS 67202-1775

April 17, 2003

Re: HOLMES H #1
API 15-007-20472-00-01
SENE 5-34S-13W, 3300 FSL 660 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888