

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Meade County. Sec. 12 Twp. 35S Rge. 27W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____


C SW SW
Lease Owner Tucker Production Corporation
Lease Name Fincham Well No. 1
Office Address 2546 W. Main, Littleton, CO. 80120
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole
Date Well completed August 8 1981
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced August 8 1981
Plugging completed August 8 1981
Reason for abandonment of well or producing formation _____

Dry Hole
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr. Grd. Cty
Producing formation. _____ Depth to top _____ Bottom _____ Total Depth of Well 6885'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1221'	8-5/8"	1221'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged Hole w/60 sax cement @ 6100',
w/50 sax cement @ 1200',
w/25 sax cement @ 400',
w/10 sax cement from 40' to 0',
w/ 5 sax cement in rat hole, &
w/ 5 sax cement in mouse hole.

Job completed @ 12:45 A.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


John R. Bartholomew of Sage Drilling Co. being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
222 Sutton Place, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1981

Louise K. Whitted
Notary Public.

My commission expires _____



RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

FINCHAM NO. 1

CASING RECORD:	OPERATOR:	Tucker Production Corp.	DESCRIPTION:
8-5/8" set @ 1221' w/650 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	C SW SW Sec. 12-35S-27W Meade County, Kansas
TOTAL DEPTH:	COMMENCED:	July 22, 1981	
6885'	COMPLETED:	August 7, 1981	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand & Red Bed	0	530	
Red Bed	530	1225	
Red Bed & Anhydrite	1225	2595	
Shale & Lime	2595	2830	
Lime & Shale	2830	5025	
Shale & Lime	5025	5280	
Lime & Shale	5280	5605	
Shale & Lime	5605	5678	
Lime & Shale	5678	5865	
Shale & Lime	5865	5990	
Lime & Shale	5990	6150	Ran DST#1 @ 6014'
Shale & Lime	6150	6280	Ran DST#2 @ 6168'
Lime	6280	6374	Ran DST#3 @ 6274'
Lime & Shale	6374	6682	
Shale & Lime	6682	6730	
Lime & Shale	6730	6878	
Shale & Lime	6878	6885	Logged Hole. Ran DST#4. D & A.

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

RECEIVED SAGE DRILLING CO., INC.
STATE CORPORATION COMMISSION

AUG 21 1981

By John R. Bartholomew
John R. Bartholomew
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 20th day of August, 1981.

LOUISE K. WHITTED
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Expires 11-26-82

Louise K. Whitted
Louise K. Whitted, Notary Public