

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Meade County, Sec. 8 Twp. 35-S Rge. 27-XX W (W)

Location as "NE/CNW/SW" or footage from lines SW/4 NE/4
Lease Owner Apache Corporation
Lease Name Judy-Myers Unit Well No. 1
Office Address 823 S. Detroit, Tulsa 20, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 21 19 62
Application for plugging filed May 22 19 62
Application for plugging approved May 23 19 62
Plugging commenced May 21 19 62
Plugging completed May 21 19 62
Reason for abandonment of well or producing formation No production

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. C. Lackamp
Producing formation No production Depth to top Bottom Total Depth of Well 6570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---------------|---------|------|------|--------|---------|------------|
| Council Grove | | 3068 | 3068 | 8-5/8" | 1156.70 | None |
| Morrow Sand | | 6022 | 6068 | | | |
| Miss. Chester | | 6116 | 6506 | | | |
| Chester Sand | | 6494 | 6506 | | | |
| St. Genevieve | | 6515 | 6570 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud laden fluid w/hulls added; through drill pipe using rotary mud pump. Laid down drill pipe and spotted 25 sx cement @ 450'. Placed a 35' cement plug in top of 8-5/8" surface casing at least 4' below ground level.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynn Drilling Company
Address 1403 National Bank of Tulsa Building, Tulsa 3, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Lloyd D. Somers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd D. Somers
823 S. Detroit, Tulsa 20, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of May, 19 62

My commission expires January 7, 1963

Notary Public

ROTARY DRILLING LOG

Operator: Apache Corporation
Judy-Myers Unit, No.1
 SW NE Sec 8-35S-27W
 Meade County, Kansas

CONTRACTOR: Lynn Drilling Co.
 Commenced: April 29, 1962
 Completed: May 21, 1962

Set 8-5/8" OD surface casing
 @ 1156.70' with 400 sax Posmix
 & 4% added gel and 150 sax common
 w/ 2% Ca Cl.

| | | |
|-------------|----------------------|-------------|
| Formations: | Shale, shells & sand | 0 - 100' |
| | Red bed & sand | 100' - 1148 |
| | Red bed & shale | 1148 - 2193 |
| | Shale & shells | 2193 - 2266 |
| | Shale & anhydrite | 2266 - 2822 |
| | Lime | 2822 - 2945 |
| | Lime & shale | 2945 - 3124 |
| | Lime | 3124 - 3282 |
| | Shale | 3282 - 3504 |
| | Lime & shale | 3504 - 3895 |
| | Shale | 3895 - 4017 |
| | Lime | 4017 - 4320 |
| | Shale | 4320 - 4480 |
| | Lime | 4480 - 4724 |
| | Lime & shale | 4724 - 4848 |
| | Lime | 4848 - 5216 |
| | Shale & lime | 5216 - 5264 |
| | Lime | 5264 - 5350 |
| | Lime & shale | 5350 - 5405 |
| | Lime | 5405 - 5505 |
| | Lime & shale | 5505 - 5556 |
| | Lime | 5556 - 5632 |
| | Shale & lime | 5632 - 5990 |
| | Shale & sandy lime | 5990 - 6052 |
| | Lime & sand | 6052 - 6080 |
| | Lime & shale | 6080 - 6124 |
| | Lime | 6124 - 6191 |
| | Lime & shale | 6191 - 6322 |
| | Lime | 6322 - 6512 |
| | Lime & shale | 6512 - 6546 |
| | Lime | 6546 - 6570 |
| | Total Depth | 6570' |

RECEIVED
 STATE CORPORATION COMMISSION

JUN 1 1962
 CONSERVATION DIVISION
 Wichita, Kansas

I, Loyd D. Somers, do certify the above log is true and correct to the best of my knowledge and belief.

Loyd D. Somers
 Loyd D. Somers,
 General Superintendent for
 Apache Corporation

Subscribed and sworn to before me this 31st day of May, 1962.

LAWRENCE A. GATZ, Notary Public
 in and for the State of Oklahoma
 My Commission Expires January 7, 1963

Lawrence A. Gatz
 Notary Public