


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Meade County, Sec. 4 Twp. 35S Rge. 27W (X) XXXX  
Location as "NE/CNW/SW" or footage from lines 1250' E of WL; 1420' N of SL  
Lease Owner Cities Service Oil Company  
Lease Name Thonhoff "B" Well No. 1  
Office Address Box 1098, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed 11-23 1964  
Application for plugging filed 1-10 1972  
Application for plugging approved 1-12 1972  
Plugging commenced 3-16 1972  
Plugging completed 3-20 1972  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 12-1 1970  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves  
Producing formation Council Grove Depth to top 3230 Bottom 3201' Total Depth of Well 6865 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Gas	3199'	3236'	5-1/2"	6862'	222'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

2800' - 2940'	20 sx cement
312' - 2800'	Mud
205' - 312'	35 sx cement
45' - 205'	Mud
0' - 45'	15 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargent's Casing Pulling Service  
Address Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
C. A. Nenny (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Nenny  
Box 1098, Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of March, 1972  
B. J. McGriff  
Notary Public.

My commission expires 8-6-74

15-119-30000-0000

1250' E OF WL & 1420' N OF SL  
SECTION 4-35S-27W  
MEADE COUNTY, KANSAS

THONHOFF "B" WELL NO. 1

CONTRACTORS: THE R. W. RINE DRILLING COMPANY

STARTED: OCTOBER 6, 1964

COMPLETED: OCTOBER 29, 1964

L O G

Sand & Shells	0' - 160'
Sand & Gravel	160' - 180'
Red Bed	180' - 1135'
Red Bed & Anhydrite	1135' - 1252'
Red Bed, Shale & Gypsum	1252' - 1635'
Red Bed & Shale	1635' - 2350'
Lime & Shale	2350' - 2568'
Lime	2568' - 2686'
Shale & Lime	2686' - 2991'
Lime & Dolomite	2991' - 3065'
Lime & Shale	3065' - 3241'
Lime	3241' - 3320'
Lime & Shale	3320' - 3924'
Lime, Shale & Dolomite	3924' - 4049'
Lime & Shale	4049' - 4503'
Lime	4503' - 4618'
Lime & Shale	4618' - 4926'
Lime	4926' - 5160'
Sand, Soft Lime	5160' - 5200'
Lime & Chert	5200' - 5216'
Lime	5216' - 5380'
Lime & Chert	5380' - 5447'
Lime	5447' - 5748'
Lime & Chert	5748' - 5789'
Lime	5789' - 5881'
Lime & Shale	5881' - 5986'
Lime	5986' - 6035'
Lime & Cherty Lime	6035' - 6084'
Lime	6084' - 6765'
Sandy Limestone	6765' - 6796'
Lime	6796' - 6865'

8 5/8" @ 1251' w/670 poz.

Totco @ 2366', 1°

Totco @ 3980', 3/4°

Totco @ 5010', 1°

Totco @ 5780', 1 3/4°


Totco @ 6575', 1 3/4°

5 1/2" @ 6862', DV @ 3331'. First stage cemented w/150 sxs. poz., second stage w/125 sxs. poz.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1972  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK) ss

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Thonhoff "B" Well No. 1 located 1250' E of WL and 1420' N of SL of Section 28-33S-32W, Meade County, Kansas.



*R. M. Green*  
R. M. Green, Secretary-Treasurer

Subscribed and sworn to before me this 3rd day of November, 1964.

*Loren E. Lake*  
Loren E. Lake, Notary Public

My Commission Expires: 6/14/66