

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20784-00-00

LEASE NAME Bernnie

RECEIVED  
JUL 29 2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Zinke & Trumbo, Inc.

SEC. 1 TWP. 355 RGE. 27 (E) or (W)

ADDRESS 1202 E. 33rd St. / Suite 100 Tulsa, Okla 74105

COUNTY Meade

PHONE# (602)-624-0156 OPERATORS LICENSE NO. 08060

Date Well Completed 3-8-89

Character of Well Gas

Plugging Commenced 7-15-02

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-17-02

The plugging proposal was approved on 4-26-02 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Basal Chester Depth to Top 6345 Bottom 6358 T.D. 6500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		576	0	8-5/8	576	0
		6500	0	4-1/2	6500	2712

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Rods & tubing were removed from wellbore 9.5lb 36vis mud. was displaced then CIBP was set @6300' with 2 sx cement on top. Casing was cut @2712' Cement plugs were placed as follows. 50 sx 1200-1050'. 50 sx. 600-450'. 10 sx. 40' to surface. All circulated thru the 4 1/2" casing while pulling out of hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jerry Dunkin, Inc. License No. 8733

Address P.O. Box 389 Enid, Oklahoma 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinke & Trumbo, Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill, Agent for Zinke & Trumbo, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Crown Consulting, Inc.

SUBSCRIBED AND SWORN TO before me this 25th day of July, 2002

[Signature]  
Notary Public

My Commission Expires:

NOTARY PUBLIC, State of Kansas  
Seward County  
HELEN M. SMITH  
My Appl. Exp. 2-5-2005

Form CP-4  
Revised 05-88

OR