

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-119-20664-0000

API NUMBER 19-20664

LEASE NAME Ediger

WELL NUMBER 1-5

430 Ft. from W Section Line

330 Ft. from N Section Line

SEC. 5 TWP. 35 SRGE. 26 W (E) or (W)

COUNTY Meade

Date Well Completed 7-22-84

Plugging Commenced 2-4-93

Plugging Completed 2-8-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Zinke & Trumbo, Ltd.

ADDRESS 1202 E 33rd, Suite 100 Tulsa, Oklahoma 74105

PHONE # <sup>918</sup> 743-5096 OPERATORS LICENSE NO. 8060

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-4-93 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5936 Bottom 5910 T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	gas	5936	5910	8 5/8	1517	0
				4 1/2	6296	2832

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 2 sks. of hulls to 5800

Pump 50 sks. of cement from 1550 to 1450

Pump 40 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE CORPORATION COMMISSION RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinke & Trumbo, Ltd

MAR 18 1993

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill

(Employee of Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 1816, Liberal, KS 67905-1816

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 93

[Signature]

Notary Public

My Commission Expires 2-5-97  
NOTARY PUBLIC, State of Kansas  
Seward County  
HELEN M. SMITH  
My Appt. Exp. 2-5-97