

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

CLARK County. Sec. 10 Twp. 35S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C SW/4 NW/4

Lease Owner DAVIDOR & DAVIDOR, INC.

Lease Name NOBLE COOK Well No. 1-10

Office Address 4515 N. SANTA FE, OKLAHOMA CITY, OKLA.

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed MARCH 30 19 64

Application for plugging filed MARCH 30 19 64

Application for plugging approved MARCH 30 19 64

Plugging commenced 11:30 P.M. ON MARCH 30 19 64

Plugging completed MARCH 31 19 64

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS (UNABLE TO CONTACT MR. SCOTT)

Producing formation NONE Depth to top Bottom Total Depth of Well 5790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	595'	8-5/8"	595'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

HOLE FILLED WITH HEAVY MUD, BRIDGE SET AT 625' FROM SURFACE, PUMPED 25 SACKS CEMENT OPEN ENDED THROUGH DRILL PIPE WHICH LEFT APPROXIMATELY 40' OF CEMENT IN BOTTOM OF 8-5/8" SURFACE CASING. SET SECOND BRIDGE AT 40' FROM SURFACE, THEN FILLED UP 8-5/8" SURFACE CASING WITH CEMENT TO BOTTOM OF CELLAR, SURFACE CASING CUT OFF THERE, SERVICE PERFORMED BY DOWELL, INC., AND JOB COMPLETE AT 7:30 A.M. ON MARCH 31, 1964.

RECEIVED
STATE CORPORATION COMMISSION

APR 2 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ROTARY DRILLING CONTRACTOR - PATTON DRILLING COMPANY, WICHITA, KANSAS
Address 505 ORPHEUM BUILDING

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.

HAROLD DAVIDOR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Davidor

4515 N. SANTA FE, OKLAHOMA CITY, OKLA.
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of APRIL, 1964

My commission expires JULY 31, 1966

Notary Public.

ROTARY WELL LOG

Davidor & Davidor, Inc. #1-10 Noble Cook
 100' East of C SW NW Section 10-35S-22W
 Clark County, Kansas

Commenced: 3/13/64
 Completed: 3/31/64
 Total Depth: 5790 ft. (measured from kelly bushings)
 Contractor: Patton Drilling Company, Inc.
 Surface Pipe: 8-5/8" @ 596' W/620 sx.
 Production Casing: None, D&A

All measurements from kelly bushings

Red bed & shells	0	to	513 ft.
No returns			596
Red bed & shells			900
Red bed & shale w/shells			1810
Anhydrite & shale			2070
Lime & shale			2301
Shale & lime			2461
Lime & shale			2635
Shale & lime			2887
Lime & shale			2991
Shale & lime			3243
Lime & shale			3354
Shale & lime			3496
Shale & chalky lime			3603
Lime			3736
Shale & chalkd lime			3937
Shale & lime			3995
Lime & shale			4102
Shale & lime			4221
Lime & sandy shale			4357
Lime & shale			4628
Lime			5282
Lime & shale			5345
Shale & lime			5401
Lime & shale			5528
Shale & lime			5630
Lime & shale			5782
Lime (5790 (Rotary Total Depth)

RECEIVED
 STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PATTON DRILLING COMPANY, INC.

BY Robert W. Patton
 Robert W. Patton, Vice President

Subscribed and sworn to before me this 2nd day of April, 1964

Lerene Schornjok
 Lerene Schornjok, Notary Public

My Commission Expires August 7, 1966

