

15-129-10492-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 5-1-57

LEASE NAME Interstate Unit

WELL NUMBER 6\*

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 9 TWP. 34S RGE. 43 ~~XX~~ or (W)

COUNTY Morton

Date Well Completed 5-8-57

Plugging Commenced 8-18-91

Plugging Completed 8-20-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-17-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 4264 Bottom 4309 T.D. 4400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				7"	1208	0
				4 1/2	4380	1818

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set MIRU csg pullers. TIH w/1 1/4 tbg to 4220, circ hole w/mud. Spot 20 sxs cmt plg from 4220-4020. TOH w/1 1/4 tbg. Shot off 4 1/2 csg @ 1818. Spot 30 sxs cmt plg from 1868-1768, spot 50 sxs cmt plg from 1300-1100, spot 30 sxs cmt plg from 650-550, spot 10 sxs from 33-3'. Cut off 3' below ground level and cap well. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams - Engineering Technician (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

Beverly J. Williams - Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

\*Formerly PEPL Interstate "D" No. 1

RECEIVED SUBSCRIBED AND SWORN TO before me this 4th day of September, 19 91  
STATE CORPORATION COMMISSION

C Cheryl Steers  
Notary Public

SEP 06 1991 My Commission Expires:

