

15-129-10560-0006

Formerly Smith "B" No. 1

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Interstate Unit

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 5

660 Ft. from S Section Line

658 Ft. from E Section Line

SEC. 8 TWP. 34S RGE. 43 (X) or (W)

COUNTY Morton

Date Well Completed 11/26/57

Plugging Commenced 11/9/87

Plugging Completed 11/12/87

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#( 316 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/8/87 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Drillers Log attached

Producing Formation Morrow Depth to Top 4309 Bottom 4313 T.D. 4410

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>4309</u>	<u>4313</u>	<u>7.0</u>	<u>1238</u>	<u>0</u>
				<u>4.5</u>	<u>4397</u>	<u>2207</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 35 sxs cement thru tubing from 4311-3961. Shot off 4.5" casing 2207, spotted 30 sxs cement from 2200-2100, spot 40 sxs cement from 1400-1125, spotted 40 sxs cement 630-450. Pushed wooden wiper plug to 50'. Spotted 10 sxs cement from 50-3'. Cut off and cap 7" casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1987

Beverly J. Williams  
Notary Public

My Commission Expires: Nov. 24, 1990

DEC 31 1987  
12-31-87  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-4  
Revised 07-87

15-129-10560-0000

DRILLER'S LOG

WELL NAME: SMITH "B" #01 WELL LOCATION: 660 ft. North of South line,  
and 1609 ft. East of West line, (C SE SE) Sec. 8, Twp. 36N, Rge. 43W,  
Horton County, Kansas. Elevation: 3591 ft. G.L.

COMPANY: Panhandle Eastern Pipe Line Company, Box #979, Liberal, Kansas

CONTRACTOR: Tony Ward Drilling Co., 1115 Liberty Bank Bldg., Oklahoma City, Okla.

DRILLING COMMENCED: 10-21-57

PRODUCTION INFORMATION:

DRILLING COMPLETED: 11-8-57

WELL COMPLETED: 11-22-57

WELL CONNECTED:

SOURCE OF DATA: Driller's Reports

ROTARY LOG

Description of Formation	Top	Bottom
Clay	0	862
Red Bed & Shale	862	1126
Red Bed & Gyp	1126	1237
Red Bed & Shale	1237	1850
Shale & Gyp w/Sand	1850	2185
Shale & Gyp	2185	2511
Shale	2511	3160
Shale & Sdy. Linc	3160	3324
Shale & Linc	3324	4244
Shale	4244	4280
Shale, Linc & Sand	4280	4311
Shale & Sand	4311	4410 TD

FORMATIONS	Tops
Wabaunsee	2603
Topeka	2803
Lansing	3283
Cherokee	3930
Horrow Shale	4250
U. Horrow Sand	4292
U. Horrow Sand	4307

\*Producing Formation(s)

PERFORATIONS:

4309-13 w/h sh/ft  
4309-11 w/h sh/ft

WELL TREATMENT RECORD:

A/500 gals HA - 11-13-57  
Treat w/200 gals 15% Acid 11-18-57  
A/500 gals HA - 11-22-57

DEC 31 1987  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

WELL NAME: **WIRTH "B" #01** WELL LOCATION: **660** ft. **North** of **South** line,  
 and **1609** ft. **East** of **West** line, (**0 SE 8E**) Sec. **8**, Twp. **34S**, Rge. **43W**,  
**Morton** County, Kansas. Elevation: **3591** ft. G.L.

COMPANY: Panhandle Eastern Pipe Line Company, Box #979, Liberal, Kansas

CONTRACTOR: **Tosny Ward Drilling Co., 1115 Liberty Bank Bldg., Oklahoma City, Okla.**

DRILLING COMMENCED: **10-21-57**  
 DRILLING COMPLETED: **11-8-57**  
 WELL COMPLETED: **11-26-57**  
 WELL CONNECTED:

PRODUCTION INFORMATION:

SOURCE OF DATA: Driller's Reports

ROTARY LOG

Description of Formation	Top	Bottom
Clay	0	862
Red Bed & Shale	862	1126
Red Bed & Gyp	1126	1237
Red Bed & Shale	1237	1650
Shale & Gyp w/sand	1650	2185
Shale & Gyp	2185	2511
Shale	2511	3160
Shale & Sdy. Lime	3160	3324
Shale & Lime	3324	4211
Shale	4211	4280
Shale, Lime & Sand	4280	4311
Shale & Sand	4311	4410 TD

FORMATIONS	Tops
abundance	2603
Topeka	2803
Lansing	3288
Cherokee	3930
Harrow Shale	4250
U. Harrow Sand	4292
U. Harrow Sand	4307

\*Producing Formation(s)

PERFORATIONS:

4309-13 w/L 24/ft  
 4309-11 w/L 24/ft

WELL TREATMENT RECORD:

1/500 gals HA - 11-13-57  
 Treat w/200 gals 15% Acid 11-12-57  
 1/500 gals HA - 11-22-57

OCT 23 1957

CONSERVATION DIVISION  
 Wichita, Kansas