

15-129-10399-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT\*

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 8 TWP. 34SRGE. 43 COR(W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 1/12/59

Character of Well Oil

Plugging Commenced 6/4/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/7/87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Physical Production

Is ACO-1 filed? Reports Filed if not, Is well log attached? yes

Producing Formation Purdy Morrow Depth to Top 4302 Bottom 4310 T.D. 4374

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation     | Content    | From        | To          | Size          | Put In       | Pulled out   |
|---------------|------------|-------------|-------------|---------------|--------------|--------------|
| <u>Morrow</u> | <u>Oil</u> | <u>4302</u> | <u>4310</u> | <u>8.625"</u> | <u>1245'</u> | <u>0'</u>    |
|               |            |             |             | <u>5.5</u>    | <u>4374'</u> | <u>2425'</u> |
|               |            |             |             |               |              |              |
|               |            |             |             |               |              |              |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP @ 4100'. Spotted 20 sxs cement through tubing from 4100' to 3950'. Shot off 5.5" casing at 2425', spotted 30 sxs cement from 2420' to 2320', 40 sxs cement from 1345' to 1145', 35 sxs cement from 650' to 480' and 10 sxs cement from 50' to 3'. Cut off and capped 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

David W. Kapple, Division Production Engineer (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P. O. Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of July, 19 87

My Commission Expires: November 21, 1990  
Notary Public, STATE CORPORATION COMMISSION

\*Formerly J. M. Huber Corp. Government "A" No.6