

15-129-10394-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 9-20-57

LEASE NAME Interstate Unit \*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 8 TWP. 34S RGE. 43 ~~W~~ (W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 10-1-57

Character of Well Oil

Plugging Commenced 4-30-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-4-92

The plugging proposal was approved on 4-29-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 4312 Bottom 4324 T.O. 4385

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1251	0
				5 1/2	4384	2233

CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mix 1 sk hulls & 15 sxs cmt & spot plug @ 4312-4212'. Circ hole w/mud. TOH w/2-7/8" tbg. Shot 5-1/2" csg @ 2424', would not come loose, shot & pulled free @ 2233'. Pmp 25 sxs cmt @ 2200-2100', 40 sxs cmt @ 1280-1180', 30 sxs cmt @ 650-550', 10 sxs cmt @ 40-3'. Cut off 8-5/8" csg 3' below GL. Rec 57 its (2233') 5-1/2" csg. KCC witness - Glenn Barlow. Restore location.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams  
Beverly J. Williams, Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

\*Formerly J.M. Huber Government "B" No. 1

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 92

Cheryl Steers  
Notary Public

My Commission Expires: \_\_\_\_\_

CHERYL STEERS  
Notary Public - State of Kansas  
My Appt. Expires 6-1-93