

15-129-10217-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA (SPUD 11/03/65)

LEASE NAME SMITH "B"

WELL NUMBER 4

1451' Ft. from S Section Line

1386' Ft. from W Section Line

SEC. 08 TWP. 34S RGE 43 (E) or (W)

COUNTY MORTON

Date Well Completed 11/14/65

Plugging Commenced 04/16/97

Plugging Completed 04/16/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/03/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation RED CAVE Depth to Top 1301' Bottom 1345' T.D. 1345'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
RED CAVE	GAS	1301'	1345'	7"	1300'	4'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU. TH W/1-1/4" TBG TO 1300'. CIRC HOLE W/9 PPG MUD. PMP 32 SXS CMT W/2 SXS HULLS TO PLG 1300-1134'. TOH W/TBG TO 300'. PMP PLG FROM 300- 134' W/32 SXS CMT. TOH W/TBG TO 40'. PMP PLG FROM 40'-SF. RDMD PU. CUT OFF & CAP 7" CSG 4' BELOW GL. KCC REP: GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KS 67905-1598 PHONE: (316) 624-3879

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God

(Signature) John A. Broman


JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1997

Shirley J Childers
Notary Public

My Commission Expires: 11/14/98



RECEIVED
KANSAS CORP
1997 JUN 20 P 1:13