

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Interstate Unit

WELL NUMBER 4

660 Ft. from S Section Line

1975 Ft. from E Section Line

SEC. 8 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 1/11/58

Plugging Commenced 11/3/87

Plugging Completed 11/9/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/2/87 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Drillers log attached

Producing Formation Morrow Depth to Top 4324 Bottom 4334 T.D. 4404

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>4324</u>	<u>4334</u>	<u>7.000</u>	<u>1256</u>	<u>0</u>
				<u>4.5</u>	<u>4044</u>	<u>2014</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 4100. Spotted 20 sxs cement thru tubing from 4100-3900. Shot-off 4-1/2" casing @

2014'. Spotted 30 sxs cement from 2000-1900, spotted 40 sxs cement from 1425-1175, spotted 35 sxs from 650-480. Push wooden wiper plug to 50'. Spot 10 sxs cement from 50'-3'. Cut off and cap 7" casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or (~~XXXXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of December, 1987

My Commission Expires: Nov 24 1990  
Beverly J. Williams  
Notary Public

12-31-87  
DEC 31 1987

15-129-10561-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION-CONSERVATION DIVISION  
211 North Broadway - Wichita 2, Kansas

DATE AND AFFIDAVIT (File one Copy)

(On Cementing in Surface or Drive Pipe as required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137, and 55-138, 1947 Supplement to G. S. Kansas 1935)

Lease Owner Panhandle Eastern Pipe Line Co.

Office Address Box 979, Liberal, Kansas

Lease Name Smith Well No. "B" 02

Well Location (Example: C N/2 NE/4 NE/4 or footage from lines)  
C SW SE SEC 8 TWP 34 RGE 43 (E) County Morton

Contractor Tommy Ward Drilling Co.

Office Address 1415 Liberty Bank Bldg., Oklahoma City, Oklahoma

Drilled with (cable) (Rotary) tools. Date pipe set November 11 1957

SURFACE HOLD DATA

SURFACE PIPE DATA

Size of Hole 9" Csg. (New) (Used) Size 7" Wt. 20#

Depth 1269' Where set 1256'

METHOD OF CEMENTING

(a) Cement: Amount and kind 450 sacks common cement

Method: (By Service Co., Dump, Tbg., etc.) Halliburton Oil Well Cmtg. Co.

Est. Height Cement behind pipe Cemented bottom to top

(b) Cementing Material: Explain method. (Example: 8-5/8 w/ swag nipple run inside 15", Bridge hold w/ rock and hole filled with cementing material. 15" pipe pulled.)

Cement circulated, cemented bottom to top

Describe cementing material Halliburton Oil Well Cementing Co.

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum

Name of lowest fresh water producing stratum

Surface elevation of well 3614.35'

ADDITIONAL INFORMATION

OCT 23 1937

(Additional information may be submitted on separate sheet)

A F F I D A V I T

STATE OF Kansas, COUNTY OF Seward SS,

I, S. H. Neithercoat of the Panhandle Eastern Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Subscribed and sworn to before me this 14 day of November 1957

My Commission Expires: Carl L. Holland  
Notary Public