

LEASE NAME Red Cave

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 5

1250 Ft. from Section Line

1250 Ft. from E Section Line

SEC. 7 TWP. 34S RGE. 43W (E) or (W)

COUNTY Morton

LEASE OPERATOR Edgar White

ADDRESS 701 Vilymaca Street Elkhart, Kansas 67950

PHONE# (316) 697-2163 OPERATORS LICENSE NO. 5156

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-6-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 1400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	473	0
				4 1/2	1458	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 1 sk. of hulls from 1406 to 1200

Pump 30 sks. of cement from 500 to 300

Pump 50 sks. of cement from 50 to 0

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O.Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Edgar White

STATE OF Kansas COUNTY OF Morton, ss.

EDGAR W. WHITE

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar White

701 VILYMACA P O DRAWER "0"

(Address) ELKHART KANSAS 67950



BEFORE AND SWORN TO before me this 15th day of JANUARY, 19 93

Karen E. Knepp
Notary Public

My Commission Expires: AUGUST 4, 1996

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1993
CONSOLIDATION DIVISION
WICHITA, KANSAS

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Red Cave #5
NE/4 Sec 7-34S-43W
Morton County Kansas

Commenced: 10-6-79

Completed: 10-8-79

OPERATOR: Edgar W. White

Depth		Formation	Remarks
From	To		
0	162	Sand	Ran 12 jts of 8 5/8" csg set @ 473' Cemented w/ 375 sks Common 3% CC PD @ 12:30 a.m. 10-7-79
162	476	Redbed	
476	1040	Sand	
1040	1270	Shale	
1270	1460	Sand-Shale	

1460 - TD

Ran 37 jts of 10# 4 1/2" csg
set @ 1458' Cemented w/
200 sks H.L. - 75 sks
Regular
PD @ 6:30 p.m. 10-8-79

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 10th day of October, 1979.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1979

CONSERVATION DIVISION
Wichita, Kansas

NOTARY PUBLIC

Exh. "A" p.3