

15-129-00007-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Morton County. Sec. 3 Twp. 34 Rge. 43 (E) (W)
Location as "NE/CNW/SW" or footage from lines 330' N & 330' E of C
Lease Owner Panhandle Eastern Pipe Line Company
Lease Name Oberley Well No. 1-3
Office Address P. O. Box 828, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 3-24 19 55
Application for plugging filed 7-20 19 65
Application for plugging approved 7-21 19 65
Plugging commenced 7-21 19 65
Plugging completed 7-27 19 65
Reason for abandonment of well or producing formation Well sanded off.

If a producing well is abandoned, date of last production 4-7 19 65
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Lansing Depth to top 3131 Bottom 3250 Total Depth of Well 3250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Wabaunsee		2664		10-3/4	657	None
Topeka		2895		7"	3249	2005
Lansing		3131				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented from 2730' to 2650' filled with mud to 650'. Set cement plug from 650' to 550', filled with mud to 45'. Set cement plug from 45' to 10'. Cut off 10-3/4" 10' below surface and welded on cap.

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling Service
Address 1546 Clay Court, Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
J. P. Phillippe (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. P. Phillippe
P. O. Box 828, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of November, 19 65

My commission expires September 13, 1966

Joan Taylor
JOAN TAYLOR Notary Public.

15-129-00007-0000

DRILLER'S LOG

WELL NAME: Oberley #1-3; COMPANY OPERATING: Panhandle Eastern Pipe Line Co.
 ADDRESS of COMPANY: P. O. Box 828, Liberal, Kansas

WELL LOCATION: SW 1/4 NE 1/4,
2956 ft. North of South line,
2970 ft. East of West line; Sec. 3, Twp. 34, Rge. 43, Morton County, Kansas

DRILLING STARTED 1-21, 19 55; DRILLING COMPLETED 1-29, 19 55
 WELL COMPLETED 3-24, 19 55; WELL CONNECTED 7-31, 19 55

ELEVATION: 3620.31 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Lansing	3130	3142	48	1000	15%
	3015	3032	28	1000	15%

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
10-3/4	657	350	None
7"	3249	300	2005

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand	0	210			
Red Bed	210	1705			
Red Bed & Shale	1705	2020			
Red Shale & Sandstone	2020	2169			
Red Bd & Sandy Anhy streaks	2169	2331			
Dolo, Lime & Shale streaks	2331	2438			
Red Shale, limestone & Dolo	2438	2571			
Lime & Shale	2571	2676			
Shale & Red Bed	2676	2785			
Lime & Shale	2785	3174			
Lime	3174	3250			
Total Depth		3250			

RECEIVED
 STATE CONSERVATION COMMISSION
 NOV 3 1965
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: O. F. 14,306 MCF