

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 129-20,909-0000

LEASE NAME St. Joan of Arc et al

WELL NUMBER 35-11

4030' Ft. from S Section Line

4030' Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed _____

Plugging Commenced _____

Plugging Completed _____

LEASE OPERATOR Tom Brown

ADDRESS P.O. Box 2608, Midland, Texas 79702

PHONE# (915) 682-9715 OPERATORS LICENSE NO. 03558

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 22, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1497'	0'
				4 1/2	3130'	2311'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 2800' w/23 ft cmt on top. Ran tbg & circ. 9# mud. Pulled tbg to 1547'. Spot 50 sx cmt. Pulled tbg to 747'. Break circ w/mud. Spot 20 sx cmt. Pulled tbg to 56'. Break circ w/mud. Spot 10 sx cmt. Cut 8 5/8 off 4' under ground level & weld 1/2" plate over top
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson License No. 05866

Address P. O. Box 1510, Liberal

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve L. Johnson

(Address) P. O. Box 2607, Midland, Tx

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 89

Barbara League
Notary Public

My Commission Expires: 05/14/90