

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Haney State Office Building  
 30 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-129-20637-0002  
 LEASE NAME LEEWE "A"  
 WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

1250 Ft. from S Section Line  
1250 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION  
 ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351  
 PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

SEC. 34 TWP. 34S RGE 43 ( E ) or ( W )  
 COUNTY MORTON

Character of Well GAS

Date Well Completed 10-6-82

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 1-28-98

Plugging Completed 1-28-98

The plugging proposal was approved on 1-17-98 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation WABAUNSEE Depth to Top 2585' Bottom 2594' T.D. 3185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
WABAUNSEE	GAS	2585	2594	8-5/8"	704	0
				4-1/2"	3184	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set. MIRU SARGENTS. PMP 1 SK HULLS & 20 SXS CMT @ 2585-2385'. PMP 65 SXS CMT @ 750-4'. PMP 15 SXS CMT DWN 4-1/2" x 8-5/8" ANNULUS. CUT OFF CSG 4' BELOW GL & CAP. RDMO SARGENTS. WITNESSED BY STATE REP. GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young  
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of February, 1998.

My Commission Expires: 11/14/98

Shirley J. Childers  
 Notary Public  
 NOTARY PUBLIC - State of Kansas  
 SHIRLEY J. CHILDEERS  
 My Appt. Exp. \_\_\_\_\_