

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-10538 ⁰⁰⁴³⁹⁻⁰⁰⁰⁰

LEASE NAME LINSCOTT

WELL NUMBER 2-33

3960 Ft. from S Section Line

1297 Ft. from W Section Line

SEC. 33 TWP. 34 RGE. 43 (E) or (W)

COUNTY MORTON

Date Well Completed 6-30-1958

Plugging Commenced 6-14-2000

Plugging Completed 6-21-2000

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-7-2000 (date)

by GARY WINTERS (KCC District Agent=s Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation TOPEKA Depth to Top 2824 Bottom 2885 T.D. 2960

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
TOPEKA	GAS	2824	2885	7"	669	0
				4-1/2"	2958	720

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. TIH W/ 1-1/2" TRG TO 2624. SPOT 2 SXS HULLS AND 20 SXS CMT FROM 2824-2624. LOAD HOLE W/ MUD. SPOT 20 SXS CMT FROM 1600-1400. SHOT OFF 4-1/2" CSG @ 720. LOAD HOLE W/ MUD. SPOT 40 SXS CMT FROM 700-500. SPOT 10 SXS CMT FROM 40-SURF. CUT OFF AND CAP 7" CSG 3' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

RECEIVED
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 3rd day of July, 2000.

CONSERVATION DIVISION
Wichita, Kansas
Commission Expires: _____

NOTARY PUBLIC - State of Kansas
SHIRLEY J. CHILDERS
My Appt. Exp. 4/1/02

Notary Public