

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 151292062500-000

LEASE NAME Lendcut

WELL NUMBER 6

2310 Ft. from ^N Section Line

2310 Ft. from E Section Line

SEC. 33 TWP. 34 RGE. 43 (X) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR San Marco Petroleum, Inc.

ADDRESS 633 17th St., Ste. 2370, Denver, CO 80202

COUNTY Morton

PHONE# (303) 291-1199 OPERATORS LICENSE NO. 31457

Date Well Completed 4/17/82

Character of Well _____

Plugging Commenced 5-31-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-4-96

The plugging proposal was approved on 5-31-96 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation Red Cave Depth to Top _____ Bottom _____ T.D. 1278
XXXX

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>4 1/2</u>		<u>0</u>
				<u>8 5/8</u>	<u>410</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Mixed 1 SK hulls to 25 sx cmt. to plug perfs from 1278 to 1078. Measured stretch on 4 1/2 - showed stuck @ 60 ft. Shot 4 1/2 @ 808 to @ 430 - Test pumped to 2500 PSI, would not take fluid. Ran 1 1/4 to 830, mixed 60 SX Plug in 4 1/2 from 830 to 0. Ran 1 1/4 down 4 1/2 - 85% annulus to 60. Mixed 15 SX plug from 60 to 0. Cut off to cap 8 5/8 4 ft. below ground level.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: San Marco Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

JUN 27 1996

San Marco Petroleum/John F. Sheridan

(Employee of Operator/Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 633 17th St., Ste. 2370

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1996

[Signature]
Notary Public

My Commission Expires: 12-17-98