

15-129-10453-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
2064 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT\*

WELL NUMBER 74

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 32 TWP. 34SRGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 6/6/55

Plugging Commenced 5/26/87

Plugging Completed 5/29/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? no if not, is well log attached? yes

Producing Formation Purdy Morrow Depth to Top 4203' Bottom 4216' T.D. 4573'

Show depth and thickness of all water, oil and gas formations..

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>4203'</u>	<u>4216'</u>	<u>8.625"</u>	<u>1247'</u>	<u>0'</u>
				<u>5.5"</u>	<u>4572.5</u>	<u>1364'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP @ 4100'. Spotted 20 sxs cement through tubing from 4100' to 3950'. Shot off 5.5" casing at 1364', spotted 50 sxs cement from 1350' to 1150', 35 sxs cement from 650' to 480' and 10 sxs cement from 50' to 3'. Cut off and capped 8.625" casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

David W. Kapple, Division Production Engineer (Employee of Operator) or ~~KXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P. O. Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of July, 19 87

Beverly J. Williams  
Notary Public  
JUL 23 1987

My Commission Expires: November 21, 1990

\*Formerly Musgrove Petroleum Corp. Wiker No.4